

TOWN OF NEW MARKET – SHADY LANE STREET IMPROVEMENT PROJECT

ADDENDUM # 1

- 1. PIPE BACKFILL METHODS SHALL CONFORM TO CURRENT VDOT STANDARDS INCLUDING BUT NOT LIMITED TO BACKFILL MATERIALS AND MEETING 95% COMPACTION DENSITY PER THE CURRENT EDITION OF THE “ROAD AND BRIDGE SPECIFICATIONS”.**
- 2. PLAN SHEET 4 OF 7 – PLAN VIEW - THE CORRECT PIPE DIAMETER BETWEEN STRUCTURES A2 AND A3 IS 30”.**
- 3. FOR BIDDING PURPOSES THE ESTIMATED E & S BOND AMOUNT IS \$7,302.00. THIS WILL BE THE CONTRACTORS RESPONSIBILITY.**
- 4. THE TOWN OF NEW MARKET WILL TAKE CARE OF RELOCATING THE EXISTING LIGHT POLES AND TELEPHONE PEDESTAL. THIS INCLUDES THE LIGHT POLE AT THE INTERSECTION OF SHADY LANE AND ROUTE 11.**
- 5. THE LOW BIDDER WILL BE ASKED TO PROVIDE A MINIMUM OF THREE REFERENCES FOR SIMILAR TYPE WORK IN THE REGION. THE TOWN OF NEW MARKET RESERVES THE RIGHT TO REJECT A BID FROM A CONTRACTOR WHO DOES NOT HAVE ANY PREVIOUS EXPERIENCE DOING SIMILAR WORK.**
- 6. AT THE COMPLETION OF THE PROJECT THE CONTRACTOR SHALL PROVIDE THE OWNER WITH A SET OF PLANS WITH ANY FIELD CHANGES MADE DURING THE COURSE OF CONSTRUCTION MARK CLEARLY IN RED PEN.**
- 7. THE TOWN WILL WORK WITH THE SELECTED CONTRACTOR TO SECURE A STAGING AND STORAGE AREA. POSSIBLE SITES INCLUDE TOWN PARK PROPERTY AND THE FIRE AND RESCUE PARKING LOT NORTH OF SHADY LANE AND NUMEROUS VACANT LOTS WITHIN THE SUBDIVISION SERVED BY SHADY LANE.**
- 8. NON-POLISHING AGGREGATE WILL NOT BE REQUIRED IN THE ASPHALT PAVEMENT.**
- 9. THE MINIMUM ASPHALT THICKNESS OVER ANY PIPE TRENCH SHALL BE 3 INCHES. THE CONTRACTOR MAY ACHIEVE THIS THICKNESS BY INSTALLING A 1 ½ INCH THICK PATCH OVER THE PIPE TRENCH FOLLOWED ULTIMATELY BY THE 1 ½ INCH OVERLAY OR THE CONTRACTOR MAY REMOVE THE NECESSARY DEPTH OF 21B AGGREGATE TO ACHIEVE THE MINIMUM 3” DEPTH WHEN THE FINAL ASPHALT OVERLAY IS INSTALLED. IN ALL CASES THE FINAL MINIMUM 21B STONE DEPTH WITHIN THE TRENCH SHALL BE 8”.**